

USD 320 Wamego-Phase 2-Bid Package 2- Multipurpose Building

Addendum 3

Issue Date: 9-29-17

Architect: BBN Architects Inc.

MEP: Orazem & Scalora Engineering, P.A.

Civil Engineer: SMH Consultants

Construction Manager: Coonrod & Associates Construction Co., Inc.

Owner: USD 320 Wamego

The attached documents and / or items below shall hereby become part of the Construction Documents for the referenced project above.


3-1: In specification section 074219-Insulated Metal Wall Panels, paragraph 2.2,B,2,b: Revise to read: ***“Exterior Finish: Two Coat Fluoropolymer”***.

3-2: In specification section 074219-Insulated Metal Wall Panels, paragraph 2.2,B,5,a: Revise to read: ***“Thermal-Resistance Value (R-Value): R-24hr*ft2*deg F BTU according to ASTM C 518”***.

3-3: In specification section 074219-Insulated Metal Wall Panels, paragraph 2.2,B,5,b: Revise to read: ***“Thermal Transmittance Value (U-Value): 0.052 Btu/hr*ft2*deg F according to ASTM C 1363”***.

3-4: The electrical contractors will be required to hook up electrical to Coonrod & Associates job site trailer at its current, onsite location. Electrical contractor to verify closest, appropriately sized circuit to tie into.

3-5: In specification section 133419-Metal Building Systems, ***Skyliner Insulation Sytems*** and ***Silvercote Lamination*** are approved manufacturers for roof insulation.



3-6: In specification section 116690-Wall Pads, ***SofStop Inc.*** is and approved manufacturer.